

Votey Hall

Re-Engineering Votey Hall:

Investment of Deferred Maintenance \$\$ into an aged Engineering Building

by: Lynn Wood

Retro-Commissioning Engineer

Physical Plant Department



Votey Hall

New Construction:

- STEM \$104M
- Central Campus Residence Hall \$70M
 - Bailey Howe Bridge
- Kalkin- Ifshin Hall \$11M
- Billings \$8.5M

Deferred Maintenance:

Votey Hall 1962 to 2017 \$5M



Votey Hall

Importance of Deferred Maintenance \$\$:

Deferred maintenance

Deferred maintenance is the practice of postponing maintenance activities such as repairs on both real property (i.e. infrastructure) and personal property (i.e. machinery) in order to save costs, meet budget funding levels, or realign available budget monies. The failure to perform needed repairs could lead to asset deterioration and ultimately asset impairment.

- 50% of Buildings that are over 50 years old
- 214 out of 243 Buildings are over 30 years old
- Mechanical and Electrical Equipment typically has a 15-20 year life cycle
- Roofs last 20-30 years Warranty for 20 years
- Code and Safety require upgrades
- Technology is constantly changing
- Utility costs continue to increase so it is important to upgrade to more efficient energy users
- Older equipment is expensive to maintain



Votey Hall

Deferred Maintenance:

- Boilers for Fleming Museum
- Roof
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Generator
- Telecom Infrastructure Replacement
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls



Votey Hall

Collaborative Effort:

- FD&C Responsible for Overall Project Costs \$10M for Renovations of Labs – part of the STEM Initiative
- Boilers for Fleming Museum –PPD Ray Doner and team
- Fire Alarm and Electrical Improvements strongly advised by Mike Enos
- AHU-1 Dual Duct & Dual Duct VAV Boxes –Davis Zone Contributions
- Controls
- Dedicated team from FD&C and PPD for Design Review
- Construction Team



Votey Hall

Construction Schedule:

Jan - May 21 – 3pm-11pm shift for rough-in and electrical

May 21 - DeEnergized Votey, Building Vacated for construction

August 1 - Energized Votey!

August 15 - Certificate of Occupancy!!

~3 months

to complete \$10M in Deferred Maintenance and Renovations



Votey Hall

Deferred Maintenance:

- Boilers for Fleming Museum
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Telecom Infrastructure Replacement
- Generator
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls



Votey Hall

Boiler Replacement:

- 2 new Boilers for Fleming Museum located in Votey
- Provides redundancy with Central Plant for reheat and dehumidification

"houses Vermont's most comprehensive collection of art and anthropological artifacts. It presents innovative exhibitions of contemporary and historic art from around the world"





Votey Hall

Deferred Maintenance:

- Boilers for Fleming
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Telecom Infrastructure Replacement
- Generator
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls




Votey Hall

Life Safety Systems:

- Code compliance with new sprinkler system
- Fire Alarm System,
 Device and Wiring
 Upgrade







Votey Hall

Deferred Maintenance:

- Boilers for Fleming
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Generator
- Telecom Infrastructure Replacement
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls



Votey Hall

Electrical Switchgear, Main Electrical Distribution, Generator:

 Before the Electrical Upgrade there was no safe PPE to wear to work on electrical equipment











Arc Flash and Shock Hazard

Appropriate PPE Required PPE Required Hazard Category 0 Nonmelting or Untreated Fiber with Arc Flash Protection Weight >= 4.5 oz/sq yd Flash Boundary 1 in Safety Glasses or Goggles + Ear Canal 0.01 cal/cm^2 Incident Energy @ 18 in ■ Leather Gloves Shock Protection Shock Hazard 480 VAC - N/A Limited Approach 42 in Restricted Approach Contact: UVM SOS (Physical Plant) Prohibited Approach Telephone: 656-2560 ("24/7" Coverage) 1 in Date: January 2013 Equipment: T-LP220 DISC





Votey Hall

Deferred Maintenance:

- Boilers for Fleming
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Generator
- Telecom Infrastructure Replacement
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls



Votey Hall

Telecom:

- Total removal of existing network infrastructure rebuilt
- Pulled over 200,000 feet of new network cable





Votey Hall

Deferred Maintenance:

- Boilers for Fleming
- Life Safety Systems
- Electrical Switchgear
- Main Electrical Distribution
- Generator
- Telecom Infrastructure Replacement
- AHU-1 Dual Duct
- Dual Duct VAV Boxes
- Controls



Votey Hall

Dual Duct AHU-1

New Chilled Water and Steam Coils







Votey Hall


Dual Duct AHU-1





Votey Hall

Dual Duct AHU-1





Votey Hall

Dual Duct AHU-1

New Dampers and Filter Banks







Votey Hall

Controls:



And some works of art left for historic purposes ... the old pneumatic panel that we decided to keep for its value as an artifact – at least in CEMS eyes:)




Votey Hall

Controls:

Upgraded to a new control panel for Dual Duct AHU-1, including over 30 Dual Duct VAV boxes, EF-1 thru 8 VFD interface























Votey Hall

Bridge to STEM:



Votey is now connected to STEMour latest addition to College of Engineering Math and Science (CEMS)...


providing impressive experiences for our learners.

"The University of Vermont's largest-ever capital project will bring a state-of-the-art STEM (science, technology, engineering and mathematics) complex of laboratories, classrooms and research facilities to campus and prepare our students for careers in rewarding, high-growth fields."



Votey Hall

And that is how our Engineering Building was Re-Engineered





Votey Hall

REMEMBERING SPECIAL TIMES AT COOK: Sometimes there just isn't enough Deferred Maintenance \$\$'s to bring a building back



THE END

